

Please type a plus sign (+) inside this box → +

**UTILITY
PATENT APPLICATION
TRANSMITTAL**

Only for new nonprovisional applications under 37 CFR 1.53(b))

Attorney Docket No. 466592000100 Total Pages 2


First Named Inventor or Application Identifier

Alain PENDERS

Express Mail Label No.

CERTIFICATE OF HAND DELIVERY

I hereby certify that this correspondence is being hand filed with the United States Patent and Trademark Office in Washington, D.C. on August 23, 2000.


Noble F. Bonds

APPLICATION ELEMENTS

See MPEP chapter 600 concerning utility patent application contents.

ADDRESS TO: Assistant Commissioner for Patents
Box Patent Application
Washington, DC 20231

1. ☒ Fee Transmittal Form
(Submit an original, and a duplicate for fee processing)
Specification [Total Pages 34]
(preferred arrangement set forth below)
- Descriptive title of the Invention
- Cross References to Related Applications
- Statement Regarding Fed sponsored R & D
- Reference to Microfiche Appendix
- Background of the Invention
- Brief Summary of the Invention
- Brief Description of the Drawings (if filed)
- Detailed Description
- Claim(s)
- Abstract of the Disclosure

2. ☒ Drawing(s) (35 USC 113) [Total Sheets 10]

3. ☒ Oath or Declaration [Total Pages 3]

a. ☐ Newly executed (original or copy)

b. ☐ Copy from a prior application (37 CFR 1.63(d)
(for continuation/divisional with Box 17 completed)
[Note Box 5 below]

i. ☐ **DELETION OF INVENTOR(S)**

Signed statement attached deleting inventor(s) named in
the prior application, see 37 CFR 1.63(d)(2) and 1.33(b)

5. ☒ Incorporation By Reference (useable if Box 4b is checked)
The entire disclosure of the prior application, from which a copy of the
oath or declaration is supplied under Box 4b, is considered as being
part of the disclosure of the accompanying application and is hereby
incorporated by reference therein.

6. ☐ Microfiche Computer Program (Appendix)
7. ☐ Nucleotide and/or Amino Acid Sequence Submission
(if applicable, all necessary)
a. ☐ Computer Readable Copy
b. ☐ Paper Copy (identical to computer copy)
c. ☐ Statement verifying identity of above copies

ACCOMPANYING APPLICATION PARTS

8. ☒ Assignment Papers (cover sheet & document(s))
9. ☐ 37 CFR 3 73(b) Statement ☐ Power of Attorney
(when there is an assignee)
10. ☐ English Translation Document (if applicable)
11. ☐ Information Disclosure
Statement (IDS)/PTO-1449 ☐ Copies of IDS
Citations
12. ☐ Preliminary Amendment
13. ☒ Return Receipt Postcard (MPEP 503)
(Should be specifically itemized)
14. ☒ Small Entity ☐ Statement filed in prior application,
Statement(s) Status still proper and desired
15. ☐ Certified Copy of Priority Document(s)
(if foreign priority is claimed)
16. ☐

17. If a **CONTINUING APPLICATION**, check appropriate box and supply the requisite information:

* ☐ Continuation ☐ Divisional ☐ Continuation-in-part (CIP) of prior application No: *

18. CORRESPONDENCE ADDRESS

Lisa E. Marks
Registration No. 44,901

Morrison & Foerster LLP
2000 Pennsylvania Avenue, N.W.
Washington, D.C. 20006-1888
Telephone: (202) 887-1500
Facsimile: (202) 887-0763

- ☒ If a paper is untimely filed in the above-referenced application by applicant or his/her representative, the Assistant Commissioner is hereby petitioned under 37 C.F.R. § 1.136(a) for the minimum extension of time required to make said paper timely. In the event a petition for extension of time is made under the provisions of this paragraph, the Assistant Commissioner is hereby requested to charge any fee required under 37 C.F.R. § 1.17(a)-(d) to **Deposit Account No. 03-1952**. However, the Assistant Commissioner is **NOT** authorized to charge the cost of the issue fee to the Deposit Account.

The filing fee has been calculated as follows:

FOR	NUMBER FILED	NUMBER EXTRA	RATE	CALCULATIONS
TOTAL CLAIMS	33 - 20 =	13	x \$18.00	\$234.00
INDEPENDENT CLAIMS	4 - 3 =	1	x \$78.00	\$78.00
MULTIPLE DEPENDENT CLAIM(S) (if applicable)			+ \$260.00	N/A
			BASIC FEE	\$690.00
TOTAL OF ABOVE CALCULATIONS =				\$1,002.00
Reduction by 1/2 for filing by small entity (Note 37 C.F.R. §§ 1.9, 1.27, 1.28). If applicable, verified statement must be attached.				\$501.00
Assignment Recording Fee (if enclosed)				\$40.00
			TOTAL =	\$541.00

Attached is the check in the amount of \$541.00

Applicant(s) hereby petitions for any required relief including extensions of time and authorizes the Assistant Commissioner to charge the cost of such petitions and/or other fees or to credit any overpayment to **Deposit Account No. 03-1952** referencing docket no. 466592000100.

Dated: August 23, 2000

Respectfully submitted,

By

Lisa E. Marks
Lisa E. Marks

Registration No. 44,901

Morrison & Foerster LLP
2000 Pennsylvania Avenue, N.W.
Washington, D.C. 20006-1888
Telephone: (202) 887-1500
Facsimile: (202) 887-0763

AUG 23 '00 10:32 FR

TO 7573#46655200012 P.02-02

Applicant/Patentee: Alain PENNERS	Sheet No.: 46655200012
Serial No./Patent No.: Unassigned	
Filed on/Issued: August 23, 2000	
For: SYSTEM AND METHOD FOR ON-LINE SERVICE CREATION	

VERIFIED STATEMENT CLAIMING SMALL ENTITY STATUS
37 C.F.R. §§ 1.9(a) AND 1.27(c) — SMALL BUSINESS CONCERN

We hereby declare that we are:

- ☐ the owner of the small business concern identified below;
☒ an official of the small business concern empowered to act on behalf of the concern identified below;

NAME OF CONCERN: Pure Matrix, Inc.

ADDRESS OF CONCERN: 6 Cebemount, Littleton, CO 80127

We hereby declare that the above identified small business concern qualifies as a small business concern as defined in 17 C.F.R. § 1.21 (2), and reproduced in 37 C.F.R. § 1.9(a), for purposes of paying reduced fees to the United States Patent and Trademark Office, in that the number of employees of the concern, including those of its affiliates, does not exceed 300 persons. For purposes of this statement, (1) the number of employees of the business concern is the average over the previous fiscal year of the number of the persons employed on a full-time, part-time or temporary basis during each of the pay periods of the fiscal year, and (2) concerns are affiliates of each other when either, directly or indirectly, one concern controls or has the power to control the other, or a third party or parties controls or has the power to control both.

We hereby declare that rights under contract or law have been conveyed to and remain with the small business concern identified above with regard to the invention, entitled **SYSTEM AND METHOD FOR ON-LINE SERVICE CREATION** by inventor(s) described in:

- ☐ the specification filed herewith with title as listed above
☐ the application identified above,
☐ the patent identified above.

If the rights held by the above identified business concern are not exclusive, each individual, concern or organization having rights in the invention must file separate verified statements averring to their status as small entities, and no rights in the invention are held by any person, other than the inventor, who would not qualify as an independent inventor under 37 C.F.R. § 1.9(a) if that person made the invention, or by any concern, which would not qualify as a small business concern under 37 C.F.R. § 1.9(a), or a nonprofit organization under 37 C.F.R. § 1.9(a).

Each person, concern or organization having any rights in the invention is listed below:

☒ Each such person, concern, or organization exists.

☐ Each such person, concern or organization is listed below:

NAME	ADDRESS	TYPE
		<input type="checkbox"/> Individual
		<input type="checkbox"/> Small Business Concern
		<input type="checkbox"/> Nonprofit Organization

Separate verified statements are required from each named person, concern or organization having rights in the invention according to their status as small entities (37 C.F.R. § 1.27).

We acknowledge the duty to file, in this application or patent, notification of any change in status resulting in loss of entitlement to small entity status prior to paying, or at the time of paying, the earliest of the issue fee or any maintenance fee due after the date on which status as a small entity is no longer appropriate. (37 C.F.R. § 1.28(b))

We hereby declare that all statements made herein of our own knowledge are true and that all statements made on information and belief are believed to be true, and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under section 1001 of Title 18 of the United States Code, and that such willful false statements may jeopardize the validity of the application, any patent issuing thereon, or any patent in which this verified statement is directed.

NAME OF PERSON SIGNING: Douglas W. McElhargh
 TITLE OF PERSON IF OTHER THAN OWNER: Vice President, Engineering
 ADDRESS OF PERSON SIGNING: 1412 Miamimont Dr. Fort Collins CO 80524

SIGNATURE: *Douglas W. McElhargh* DATE: 8/23/2000

United States Patent Application

of

Alain PENDERS

for

SYSTEM AND METHOD FOR ON-LINE SERVICE CREATION

SYSTEM AND METHOD FOR ON-LINE SERVICE CREATION

FIELD OF THE INVENTION

5 The present invention relates generally to platforms for providing services to devices, and more particularly, to a platform which allows a user of a service for a device to create, activate, and execute the service.

BACKGROUND OF THE INVENTION

10 As used herein, the term "service" generally refers to an application which performs a function for a device using a platform. A service may include, for example, displaying specified data, or sending data to a device. International Telecommunications Union (ITU) specification I.312 describes the service creation process in an intelligent network as including several steps: (1) designing the service; (2) developing, implementing, and
15 documenting the service; (3) rigorously testing the service; and (4) activating and using the service. This service creation process is typically performed-offline. It is also complex and time consuming. The Telecommunications Information Networking Architecture (TINA) describes a similar service creation process. For additional details on the TINA service creation process, see "Overall concepts and principles of TINA", version 1.0, issued 17th Feb
20 1995, or "TINA-C Glossary of Terms", version 2.0 (January 1997), both of which are herein incorporated by reference.

 Services are generally created by owners of the platform on which a device receiving the service operates, rather than by the user of the service. For example, a telephone carrier may provide a service enabling customers to define calling groups. While the customer, *i.e.*,
25 the user of the service, can define who is part of a calling group, or configure the service, the customer is not permitted to define the service enabling this access, *i.e.*, the customer is not permitted to define the calling group service itself. Rather, the long distance carrier, or the mobile telephone service provider, *i.e.*, the platform owner, creates the service. Similarly, if an investor desires to sell a security when it reaches a specific price, the investor
30 communicates the desired service request to a broker who may then implement a service to

automatically initiate a sale transaction when the security reaches the specified price. The beneficiary of the service, the investor, is not the service creator.

Thus, an end-user of a service is generally provided only with service configuration capabilities, as distinguished from service creation capabilities. Service configuration includes specifying values for a pre-defined service and unlike conventional service creation processes, may be performed on-line. For example, Internet portals, such as Pointcast™, or Yahoo!™ allow Internet users to configure the services they subscribe to. If a Pointcast™ user subscribes to a service to automatically send daily news and securities pricing information, the user may configure the service by indicating which news subject areas and securities should be included in the daily delivery. Similarly, the mobile Internet portal of Yahoo! (mobile.yahoo.com) allows users to subscribe to services for receiving e-mail, news, financial information, etc. on a mobile device, such as a mobile phone or a personal digital assistant (PDA) device. A user may configure the service by indicating which information to receive.

Because conventional service creation processes are complex and time-consuming, they do not support rapid creation of new, and customized services. Customized services, or services tailored to the desires of an end-user of the service, are undoubtedly more appealing to end-users because they will be tailored to meet the needs of the user. Most end-users do not have the knowledge or time required to design, develop, test, and implement services. Further, most end-users do not have the necessary platform accesses to introduce a service onto a platform.

Accordingly, a need exists for a manner of allowing an end-user of a device to create a service for the device without intervention from the platform owner.

SUMMARY OF THE INVENTION

The present invention provides an on-line platform which allows an end user of a device using a platform to create a generic application for delivering a service to the device. Services may also be created by, for example, content providers and content aggregators, without intervention of a platform owner. For example, a system user may create a service to automatically issue a selling order for a stock if its price reaches a certain level. The user need not contact the platform owner to create such service. Thus, an owner of a device, *i.e.*,

the end-user of a service, can create a service for the device as and when it is needed. An end-user may also modify a previously created, or pre-defined service. The invention provides these service creation capabilities for various network devices that may have either wired or wireless connectivity to the platform. Wired connectivity includes connections through networks like the Internet, as well as telephony. Wireless connectivity includes one-way or two-way wireless voice and data networks. An indirect network connection refers to a connection which is provided, at least in part, by a one- or two-way wireless voice or data network. The system guides each user through the process of creating services.

In accordance with an embodiment of the invention, a system is provided for an end-user of a service for a device using a platform owned by a platform owner to create the service. The system receives from the end-user linking information indicating a second building block to link to a first pre-defined building block. The system then creates a service based on the received linking information.

In accordance with an aspect of the invention, the system may further receive configuration information to configure the first and second pre-defined building blocks.

In accordance with another embodiment of the invention, a method is provided for an end-user of a service for a device using a platform owned by a platform owner to create the service. The end-user of the device sends to a server information to link a first, pre-defined building block to a second pre-defined building block. The service is created based on the received linking information.

In accordance with an aspect of the invention, the end-user may send to the server information to configure the first and second pre-defined building blocks.

In accordance with a further embodiment of the invention, a system is provided for an end-user of a service for a device using a platform owned by a platform owner to create the service. The system includes a server including a platform which includes a service creation interface to allow the end-user to create the service by linking a first pre-defined building block to a second pre-defined building block, and a client including an interface for interacting with the platform. The system may further allow the end-user to configure the first and second pre-defined building blocks.

The platform stores the services created by system users, and may also provide other pre-defined services, supporting even more rapid service creation. Pre-defined services may

be viewed and copied by system users, depending on the access rights assigned to the service and to a particular user. Therefore, system users do not have to create their own services, but may instead use services created by other system users, or other pre-defined services. By subscribing to pre-defined services, users may additionally learn more about the platform and the types of services that can be created with it. The system also provides users with access to the building block-level view of the pre-defined services, allowing the users to gain additional insight into the system to understand how it works and how it may be used to create a service.

In accordance with an aspect of the invention, a copy of a pre-defined service, or part thereof, may be provided to a user either upon request, or automatically upon subscription to the pre-defined service. In the latter case, the user subscribes to a personal copy of the pre-defined service. This copy may be used as a foundation for a separate customized service, *e.g.*, the user can modify the service by changing the linking between the building blocks, by changing the configuration of the building blocks, or by adding or deleting building blocks from the service.

In accordance with another aspect of the invention, a service creation interface includes a front-end and may further include an intelligent skin which is accessible through the front-end.

These and other aspects of the invention will become readily apparent to those of ordinary skill in the art from the following description of the invention which is to be read in conjunction with the accompanying drawings and appended claims.

BRIEF DESCRIPTION OF THE DRAWINGS

Figure 1 depicts an exemplary architecture on which the invention could operate;

Figure 2 depicts a logical view of the invention;

Figures 3A and 3B depict flow diagrams of the processing that occurs during configuration of a building block, and creation of a service, respectively;

Figure 4 provides further details on the Directory Services and the OpenSCE, depicted in Figure 2;

Figure 5 depicts a screen shot of an exemplary directory listing;

Figure 6 depicts additional details of the SEE;

Figure 7 depicts an example of a processing performed relative to a “push” service;
Figure 8 provides further details on the Output System, depicted in Figure 2;
Figure 9 provides further details on Service Execution Environment, depicted in
Figure 2; and
5 Figure 10 provides further details on the Data Processing System, depicted in Figure
2.

DETAILED DESCRIPTION OF THE INVENTION

The present invention provides a system and method that allows an end-user of a
10 service to create an application which delivers the service to one or more end-users.
Throughout this document, “applications” may be referred to as “services.” The system and
method provides a user-friendly manner for end-users who do not have programming skills
or service creation experience to create new services on-line. Services which are created on
this platform may also be activated, and executed on-line. The term “device,” as used herein,
15 refers to any mechanism which may be accessed through a network, either directly or
indirectly, including, for example, cellular phones, handheld computers, and Internet
appliances. The term “Internet appliance” refers to a task or function specific device which
includes an embedded computer and may be connected to a network such as the Internet.
Internet appliances may include, for example, Internet-enabled refrigerators, ovens, VCR's,
20 screenphones, and video cameras. The system and method may also be used to activate,
execute, modify, and delete services for devices.

Figure 1 depicts an exemplary architecture on which a platform that allows a system
user to create, activate, execute, modify, and delete services, could operate. Access to both
the Internet and the platform owner’s network (*e.g.*, the mobile telephony network) occurs
25 through a redundant firewall & load balancing system. Such a system can be implemented
using equipment available from, for example, Cisco™. The load balancing system ensures
that all incoming HTTP requests are sent to an active node. Each node includes the software
of the invention. A node may be, for example, a Sun™ server running the Solaris operating
system.

30 The connection from the firewall and load balancing system to the Internet, or a
platform owner’s network, can be implemented with a variety of technologies, such as,

leased lines, ethernet connections, or a synchronous transfer node (ATM). The connection from the firewall and load balancing system to the individual nodes occurs through redundant ethernet connections, which may be, for example, 100mbit or 1Gbit ethernet. The nodes are connected to redundant fiber optic cables. The fiber channel switches are connected to a fault tolerant storage array and database nodes. Through the fiber channel switches, the nodes can reach each database node and the storage array.

A database node may include one or more machines (e.g., Sun™ servers running the Solaris™ operating system) running a commercially available database server, such as Oracle. The invention software utilizes an abstraction layer which is independent of the software and configuration of the database nodes. The fault-tolerant storage array can range from a series of SCSI disk arrays with RAID 5 (fault tolerance) support to a large Storage Area Network (SAN) system, sold by, for example, EMC2. One of skill in the art will thus appreciate that a variety of storage solutions may be used.

Figure 2 depicts a logical view of the components of a platform 200 which allows a system user to create, activate, execute, modify, and delete services. A service is created by linking and configuring, as appropriate, one or more pre-defined building blocks 220. A building block provides a logical and functional step of a service. Each building block 220 includes a software program including a set of rules indicating the building block's implementation, permissions, and otherwise controlling the operation of the building block. Each building block implements a specific function that can be used to create a service. Building blocks may also include variables to which a user assigns a value. Each building block includes a configuration interface which allows a service creator to configure the building block and indicate which other building blocks, or types of building blocks, the building block may be linked to. The configuration interface guides a user through the process of configuring a building block 220 by presenting to the user step-by-step configuration inquiries until the building block 220 is completely configured. The configuration interface may further simplify the service creation process by, for example, indicating to which building blocks a particular building block can be linked. This indication may be in the form of, for example, a hyperlink which, if clicked on, links the building block to another building block, and immediately connects the end-user to the configuration

interface of the linked building block. Building blocks that only have optional parameters, or which do not have any parameters, do not require configuration.

Figure 3A depicts the processing that occurs during configuration of a building block 220. During the configuration process, each building block is capable of providing

5 information indicating the building blocks to which it can be linked. The user can select one of these specified building blocks to perform instant linking of that building block to the building block being configured. Once that selection is made, the configuration information of the current building block is saved, the new building block is linked and the configuration dialog of the new building block is opened for the user to configure the new building block.

10 When a service creator uses this functionality of the building block configuration interface to select a building block to link to, the building block returns a code from its configuration interface indicating which building block or building block types it should be linked to.

Upon receipt of this specific return code, the platform 200 directs the user to perform the linking. Each building block is graphically represented on the screen. The service creator

15 can link building blocks by selecting an existing building block, and subsequently selecting a building block to link to it. After this selection has been made, the service creation environment displays both building blocks as linked. The system confirms that the linking is proper by checking the type and linking restrictions of each building block being linked.

Building blocks can be classified in three types: start, stop, and others. Start blocks cannot
20 be linked behind another block; No blocks can be linked behind a stop block. Other blocks must be linked behind a start or other block. Linking restrictions can include such things as not being allowed to link two input blocks, and not being allowed to link a loop block (*e.g.*, for, while, etc.) to itself. Once the new building block has been linked (or is accepted as a start block), the system can begin the building block configuration process for the building

25 block. During the linking and configuration processes, no information is exchanged between the building blocks. The information regarding the linking and configuration of the building blocks for a service being created, *i.e.*, building block configuration data, is managed and stored by the OpenSCE.

Figure 3B depicts further details of how a service is created by configuring building
30 blocks. Once all of the building blocks of a service have been configured, the service creation process is complete and the service is added to the service directory.

Building blocks are developed by a third party, for example, PureMatrix™, and are installed by the owner of the platform on which they operate. Before being made available to the platform, building blocks are rigorously tested to decrease their likelihood of negatively impacting the integrity of the platform or an associated service, including, for example, the platform crashing, and data corruption. During testing, various usage patterns of the building block are analyzed to ensure that the building block functions as intended.

This testing represents one of the many levels of integrity checking which is built into the platform. The Open Service Creation Environment 228 (OpenSCE) provides a graphical user interface to create services on the platform 200. Via OpenSCE 228, a user may select, link, and configure building blocks into a functional service. Once a service has been created using the OpenSCE, it is stored in databases 232. The databases 232 also store user information, including, for example, logging and statistical data, and session data. The OpenSCE 228 is only available from HTML-enabled devices including, for example, PCs and WebTVs.

Directory services 236 displays to a user the services which may be used by that user. It includes services which were created by system users, and pre-defined applications, such as a service created by a platform owner. Directory services 236 may be organized such that services can be indexed and sorted to allow a system user to easily find and access a specific service. For example, services may be organized into directories by subject, such that sports related services may be included in a sports directory. End-users may customize each directory to their needs by, for example, moving frequently used services to the top of a directory.

In response to a user initiating execution of a service by, for example, clicking on a service link provided via the web interface, the Service Execution Environment 240 (SEE) loads the data related to a service from the database 232, and then executes it. The SEE 240 controls the overall program flow, security, privacy, and variables of the service, while each building block 220 handles the execution of its internal logic. Additional details on SEE 240 are described relative to SEE 444, with the description of Figure 6.

During the creation and execution of a service, the service can interact with external data. The Data Processing System 246 (DPS) includes logic to interface with various external data sources, to filter incoming and outgoing data, and to buffer data which is fed

into the platform 200. The interface to the external data is a program that reads, stores and analyzes the data in the format in which the data arrives at platform 200. The data may be in the form of, for example, ASCII, XML, or streaming audio, etc. When a service specifies an action to be performed with, or from, external data, DPS 246 examines the external data, and using stored information indicating acceptable use of the information, filters the data that is not used and stores, updates, or triggers events (as appropriate) from the data that is used.

Middleware layer 250 provides support functionality, such as high availability, coupling to back office, libraries, etc., to applications. For example, MatrixCORE™, which provides both active functionality, such as, interaction with databases from different vendors, handling data logging, managing failures in the platform, etc., and passive functionality in the form of libraries with generic functions, may be used as middleware layer 250.

Applications interface to the middleware layer 250 via, for example, software libraries and Application Program Interfaces (APIs). The applications are programmatically linked to the software libraries and use the APIs provided by those libraries to access the functionality provided by middleware layer 250.

Back office 254 manages the platform 200 and handles its interface with legacy systems, such as billing and user databases, etc. A legacy system is a system that already exists and exchanges data with platform 200. Back office 254 provides the interfaces needed to successfully integrate with a platform owner's legacy systems, and provides the tools needed to commercially manage the platform 200 (user provisioning, marketing tools, statistics, advertising, hardware & software management, logging, etc.). Back office 254 supports a set of flexible APIs, implemented in a software library, which are called by the back office 254 to interface with the legacy systems. The system further includes a software library that supports the API and also interfaces to the legacy system. The software library is modular in that the modules that interface the legacy systems can be removed and replaced without affecting the back office 254 implementation.

The platform 200 delivers the user-created services to target devices in a format the devices may understand by using a standard protocol, such as, Wireless Application Protocol (WAP).

Figure 4 provides further details on Directory Services 436 and OpenSCE 428. Many devices, including Wireless Application Protocol (WAP) cell phones, PDAs, I-mode cell

phones, and HTML enabled devices such as PCs, WebTVs, and Internet appliances access the platform 200 using a markup language and HTTP. All of these devices are connected to a Web Front-End (Web FE) of platform 200. The Web FE handles authentication, session management, and selection of a specific “skin” which provides a unique user interface, look, and feel to the platform. A skin, in general, uses the existing functionality of the underlying interface without extending it. Skins may, however, be used to customize the user interface of platform 200 for different customers (*e.g.* Sprint PCS, AT&T Wireless, etc.), and for different end-user groups (*e.g.*, Teenagers, Star Trek fans, employees of a company, etc.). The skins used by the platform are “intelligent skins” which can extend and modify the existing functionality of the underlying interface. “Developer skins” provide the user interface to the OpenSCE. An end-user may choose a Star Trek skin while using services, but an Advanced Generation Y Developer Skin when creating new services.

A building block instance refers to a copy of a building block, which is specifically configured to run in a particular service. OpenSCE also handles creation of each building block instance, and linking, deleting, moving, etc. of instances of a building block or a group of building blocks. The OpenSCE 428 interfaces directly with Directory Services 436 to store the service flow data and context data, and indirectly through the building blocks to store the instance data for each building block used in a service. Service flow data reflects the logical flow of the service, including the building blocks that make up the service and the links between the building blocks that define the execution logic of the service. The context data defines to whom and how a service is made available.

After a service has been created, system-users may be able to view it in their service directory, depending on the accesses assigned to the service by the creator of the service. When a user places a request to Directory Services 436 to retrieve a directory of services, Directory Services 436 loads the corresponding directory from the database, filters the entries included in the directory, and removes all services that the end-user does not have access to. Directory Services 436 then sorts the directory according to, for example, the end-user’s user profile settings and modifies the directory to reflect the changes that the end-user has indicated, such as, for example, moving often used entries to the top. Then, Advertisement System 438 modifies the directory to, for example, move advertised services to the top of the listing. Directory Services 436 returns the directory to the skin that requested it. The skin

which requested the directory is responsible for displaying the directory to the end-user.

Figure 5 depicts a screen shot of an exemplary directory listing.

When a user selects a service that is displayed in a directory, Service Execution Engine (SEE) 444 loads from Databases 232 data describing the service, and executes the service in the corresponding node, as described above. Prior to executing a service, SEE 444 may request Advertisement System 438 to display an advertisement. Advertisement system 438 determines whether to actually display an advertisement, and which advertisement to display, described further below relative to Figure 7.

10 Service Execution Engine

Figure 6 depicts additional details of the Service Execution Engine (SEE) 444. SEE 444 loads from a database a “service context” for a service to be executed. The service context includes generic data about the service, for example, to whom the service is available, where it is available, etc. If the service context includes information indicating, for example, that the specific user requesting execution of the service isn't allowed to execute it, SEE 444 returns an error message. If, on the other hand, the user is allowed to execute the service, SEE 444 loads a data map indicating how the building blocks of the service are linked. Based on this “map,” the building blocks are executed according to the specified order. The execution order may be affected by the building blocks, for example, when a conditional event determines what part of the service to execute.

The execution of each building block includes several steps: (1) the building block is loaded into memory, and initialized; (2) the building block loads its instance data from a database, *i.e.*, to load the variables that are configured for the building block; (3) the building block executes using the available instance data; (4) the building block frees the instance data by removing any locks or protection placed on that data during execution of the building block and (5) the building block is released from memory. When the building block is released from memory, the memory resources used by the building block are freed and available for other computing processes to use. These steps need not be performed each time a building block is executed because the system further utilizes various optimization algorithms to increase the execution speed. For example, a building block may only be

released from memory after sitting idle for a specified time, allowing a building block which is used twice in one service to remain in memory until the service completes execution.

Execution of a service may also be suspended by saving the execution state of the service in the database. The execution state includes the value of the variables in use by the service and the place in the service execution logic where the service was suspended. After the service execution state is stored in the database, execution of the service is terminated. When execution of the service resumes, the data is retrieved, the variable and the execution state are restored to their pre-suspension state, and the service is restarted from the suspension point. Service suspension may be used, for example, when a user has to fill out a form. After the form is sent to the user, the service execution may be suspended. When the user submits the completed form, the execution is resumed. After a service completes execution, the data associated with the service is discarded.

Once a service executes, it may provide output in the form of device-independent content data to a target device. The platform further includes a delivery back-end that converts the device independent output data of a service into a format suitable for a target device, using, for example, Wireless Application Protocol (WAP) standards. The platform further includes Content Conversion 450 to convert content from an internal device-independent format to the final output format.

Windows and Java applications

In order to speed up service creation and use, a dedicated Windows or Java application 460 and 464, respectively, may be used to access the platform 200. Such an application connects to the system via a dedicated front-end which handles security and conversion from the application protocol to the existing functions that support service creation, *e.g.*, Directory Services and OpenSCE.

Service Activation

Service activation is the process of making a new service available for execution by one or more end-users. When the service activation process is successful, the new service is made available through a service directory that is included in Directory Services 436. This

process may include various steps, depending on the configuration of the platform, the access rights of the service creator, etc. Following is an exemplary service activation process:

1. The service creator requests activation of the service by selecting a “make service available” option from the OpenSCE user interface.
- 5 2. The OpenSCE performs integrity checking on the service, including:
 - a. Determining whether each of the building blocks is configured correctly/completely. Each building block indicates this itself by ensuring that all configurable values required by the building block are initialized and contain valid values.
 - 10 b. Determining whether there at least two building blocks included in the service.
 - c. Determining whether each branch of the service has a valid ending block.
 - d. Determining whether there are any end-less loops or overly CPU-intensive aspects of the service.
 - 15 e. Determining whether the service send large amounts of data to a third party.
 - f. Determining whether the service contains adult content, and if so, whether it is listed as an adult service.
- 20 3. Verifying that the service creator is allowed to activate services he/she has created, and if not, send an activation request email to the platform administrator.
4. Determining whether the service creator needs to pay for this service, and if so, handling billing for it. If billing fails, service activation is aborted.
- 25 5. Reseting the service tracking data so that service misbehavior can be detected at run-time.
6. Informing each building block (instance) that its service has been activated. This allows each building block to initialize external data that it may need to function correctly.
- 30 7. Storing the service activation state in the service directory, so that the service can be executed.

When a user initiates execution of a service, as described above, the service is referred to as a “pull” service. Figure 7 depicts the logical components of a “push” service. A push service may be, for example, an advertisement which is sent to the end-user without the user requesting it, a reminder that the user activated earlier, a new stock quote, a “Happy birthday” message from a friend, etc. A “trigger” is an event which initiates execution of the push service. The trigger may come from a variety of sources including, for example, a timer, incoming data, or another service that is executing. Triggers are sent to the Push Service Manager 712, which sends it to a SEE 444 that will execute the service and deliver the output to the appropriate end-user(s). Which SEE 444 is used is determined by a HTTP-based load-balancing system. For interactive services, an intermediate information request is pushed to a user. By replying to pushed information, the user initiates a “pull”, and the processing described above (relative to Fig. 4) applies.

The SEE 444 may interact with Advertisement system 438 to display advertisements, either before or during the process of data being sent to a user. Advertisement System 438 requests from Directory Services 436 available advertisements. Advertisement System 438 may either select a specific advertisement based on, for example, matching the ad with user profile information, or may randomly select an ad included in a directory. The selection of advertising is managed by the product owner, using an advertisement management software tool, provided with the product. This tool permits the product owner to select, manage, configure, and track advertising activity in the product.

Figure 8 depicts Output System 810. When used in pull mode, a skin 820 passes output data, *i.e.*, data which is output from a service, to Output System 810, which converts the data into a format appropriate for the user, and passes the converted data to the user via web server 830. In push mode, Push Service Manager 838 passes the output of a service to Output System 810 which processes the data as follows: (1) it retrieves the preferred target device from the User Profile (a user may have multiple wireless devices); (2) it performs content conversion, dependent on the target device; (3) the resulting data (device dependent) is passed on to the appropriate delivery system, which usually is also device dependent (SMS, Email, WAP Push, etc.); (4) if the end-user cannot be contacted because, for example, if the end-user has declined message delivery during a specified time, the message may be stored in the Message Store 840 for later delivery.

Figure 9 provides further details on Service Execution Engine 444. Service Execution Engine 444 may be started from a skin 920, or from the Push Service Manager 712. The Service Execution Engine 444 retrieves data related to a service, including service context data and building blocks linking data from the Services Database, *i.e.*, Directory Services 436. When executing a service, the Service Execution Engine 444 interacts with Variable Management 924 (VM) which stores variables which have been defined in a service. Although not depicted in this figure, building blocks 220 may also interact with the VM 924.

VM 924 further includes integrity checking mechanisms. For each variable that VM 924 manages, the VM 924 tracks who has access to the data included in the variable. When a new variable is created using data from an existing variable, the new variable is assigned at least the same privacy settings as the existing variable. VM 924 also verifies that output data is in an appropriate form prior to the data being delivered to an end-user of a service. The VM 924 makes this determination based on information provided by each building block indicating acceptable data types for variables.

The VM 924 also stores variables and retrieves variables from Temporary Database 928 which stores the Session data, which includes the value of the variables used by the service and an indication of a place in the service execution logic where the service was suspended. A service may be suspended and subsequently resumed when, for example, a user must complete a form during service execution. The service may be suspended while the user completes the form, and resumed after the user submits the completed form.

The Push Service Manager 712 may receive triggers indicating that data needs to be sent to an end-user from Timed Services Manager 930 and the Data Processing System (DPS) 246. The Timed Services Manager 930 tracks timed services implemented on the platform 200, and sends triggers to activate each of these services. Each timed service includes a timer building block. When a timed service is activated, the timer building block contacts the Timed Services Manager 930 and passes to it data reflecting the specified time of day, day of the week, etc., needed to create a service execution trigger, in this case also known as a timer event.

Figure 10 provides further details on DPS 246. The DPS 246 interfaces with external data sources which may be used within services built on platform 200. It interfaces legacy

systems such as, for example, Oracle databases, and PeopleSoft, so that those systems can be used from within services created on platform 200. It also converts and stores various data which is fed into a service from a variety of external sources. DPS 246 may process, for example, XML and ASCII based data feeds including, for example, a Reuters™ news feed, a Bloomberg™ sports feed, a NASDAQ™ stock exchange data feed, mailing lists, Web pages, word processing files, and MP3 streaming audio and video.

All data feeds (whether unidirectional or bi-directional) can be accessed and/or controlled from one or more building blocks, DPS Building Blocks 1070 (DPSBB). The DPSBBs 1070 control what data leaves the platform, what transactions are performed on legacy systems, for example, an Oracle database. They also control the operation of the Real-time Filter 1030 which creates triggers for incoming data and stores a portion of the incoming data in the DPS Database 1038. In general, only data that is actually used in services is stored in DPS database 1038. Real-time Filter 1030 further includes its own high-speed internal database which stores filtering rules that it receives from DPSBBs 1070, enabling real-time operation.

The DPS Manager 1044 controls the interaction between the external data feeds, DPSBBs, and the DPS Database. It decides which external data feeds are allowed to connect to the platform 200, how those data feeds should be processed, what information will be made available to the DPSBBs 1070, and what information can be stored in the DPS Database 1038.

As described above, the platform 200 takes steps to confirm the integrity of services created with it. If the system fails, a “self-healing” system will detect it and deactivate the appropriate building block(s) by removing it from the database so that it cannot be used in service creation and can no longer be executed as part of a service. The platform restricts the order in which the building blocks are linked, *e.g.*, by ensuring that a service with an invalid building block ordering cannot be activated. Further, the platform may not be accessed through an interface other than the web front-end or the protocol for dedicated applications, absent the explicit permission of the platform owner. Individual building blocks may additionally have error checking parameters which the system reviews prior to activation of a service. Therefore, platform owners do not need to test services created with the platform.

Although the methods and systems of this invention have been described with reference to a specific implementation, those skilled in the art will know of various changes in form and detail which may be made without departing from the spirit and scope of the invention. The scope of the invention is therefore defined only by the appended claims and
5 the full scope of their equivalents.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
841
842
843
844
845
846
847
848
849
850
851
852
853
854
855
856
857
858
859
860
861
862
863
864
865
866
867
868
869
870
871
872
873
874
875
876
877
878
879
880
881
882
883
884
885
886
887
888
889
890
891
892
893
894
895
896
897
898
899
900
901
902
903
904
905
906
907
908
909
910
911
912
913
914
915
916
917
918
919
920
921
922
923
924
925
926
927
928
929
930
931
932
933
934
935
936
937
938
939
940
941
942
943
944
945
946
947
948
949
950
951
952
953
954
955
956
957
958
959
960
961
962
963
964
965
966
967
968
969
970
971
972
973
974
975
976
977
978
979
980
981
982
983
984
985
986
987
988
989
990
991
992
993
994
995
996
997
998
999
1000

WHAT IS CLAIMED IS:

1. A method for an end-user of a service to create the service for a device using a platform owned by a platform owner, the method comprising:
 - receiving from the end-user linking information indicating a second pre-defined building block to link to a first pre-defined building block;
 - creating the service by linking and configuring the first and second pre-defined building blocks; and
 - executing the service on the platform immediately, without testing the service.
2. The method of claim 1, further comprising receiving from the end-user configuration information to configure the first pre-defined building block.
3. The method of claim 1, further comprising creating the service based on the received configuration and linking information.
4. The method of claim 3, further comprising determining an integrity of the created service.
5. The method of claim 1, further comprising receiving from the end-user an indication of information to modify the service.
6. The method of claim 1, further comprising receiving from the end-user an indication of information to delete the service.
7. The method of claim 1, further comprising receiving from the end-user an indication of information to activate the service.
8. The method of claim 1, further comprising assigning a value to a variable of the first or second building block.
9. The method of claim 1, further comprising executing the service.

10. A system for an end-user of a service for a device using a platform to create the service, comprising:

a server;

a platform residing on the server having a service creation interface to allow the end-user to create the service by linking a first pre-defined building block to a second pre-defined building block, the service being executed without requiring any testing; and

a client comprising an interface for interacting with the service creation interface.

11. The system of claim 10, wherein the client interacts with the platform via a proxy server protocol.

12. The system of claim 10, further comprising a directory device which stores the first and second pre-defined building blocks.

13. The system of claim 10, further comprising a directory device which stores the service.

14. The system of claim 10, wherein the service creation interface prevents unauthorized users from accessing the service system.

15. The system of claim 10, wherein the device includes an Internet appliance.

16. The system of claim 10, wherein the client interface includes a dedicated client application.

17. The system of claim 10, wherein the first or second building block includes a variable to which an end user assigns a value.

18. The system of claim 10, wherein the first and second building block includes a building block configuration interface which guides the end-user through a process for configuring the building block.

19. The system of claim 10, wherein the client interface includes a web browser.

20. The system of claim 10, wherein the client interface includes a web browser having an intelligent skin.

21. The system of claim 10, wherein the device includes a mobile device.

22. The system of claim 10, wherein the created service is delivered to the device via a wireless protocol.

23. The system of claim 10, wherein the platform further includes rules for checking an integrity of the created service.

24. The system of claim 10, wherein the platform allows a user to configure the first or second building block.

25. A method for an end-user of a service to create the service for a device using a platform, comprising:

sending to a server linking information indicating a second building block to link to a first pre-defined building block;

creating the service based on the linking information; and

executing the service on the platform without testing it.

26. The method of claim 25, further comprising sending to the server an indication of configuration information to configure the first pre-defined building block.

27. The method of claim 25, further comprising creating the service according to the configuration information and the linking information.

28. The method of claim 25, wherein sending the indication of configuration information includes accessing a configuration interface included in the first pre-defined building block.

29. The method of claim 25 further comprising sending to the server an indication of information to delete the service.

30. The method of claim 25 further comprising sending to the server an indication of information to modify the service.

31. The method of claim 25 further comprising sending to the server an indication of information to activate the service.

32. A computer-readable medium having instructions for an end-user of a device using a platform owned by a platform owner to create a service for the device, comprising:
a first unit to receive from the end-user an indication of configuration information to configure a first pre-defined building block;
a second unit to receive from the end-user an indication of linking information indicating a second building block to link to the first pre-defined building block; and
a third unit to create the service based on the information received from the first and second units, wherein the service may be executed prior to being tested.

33. A computer-readable medium comprising instructions for an end-user of a device using a platform owned by a platform owner to create a service for the device, comprising:
a first unit to send from the end-user to a server configuration information to configure a first pre-defined building block;

a second unit to send from the end-user to a server linking information indicating a second building block to link to the first pre-defined building block; and
a third unit to create the service based on the configuration and linking information.

2025-03-10 10:10:10

Abstract

A system and method for on-line service creation in which end-users of a device using a platform owned by a platform owner may create a service for the device by configuring and linking pre-defined building blocks which function as the logical steps of the service. The system includes integrity checking mechanisms, and, hence, a platform owner does not need to be involved in the service creation, activation, or execution processes. The system also allows users to modify, copy, and otherwise manipulate services created by other system users, including, for example, platform owners.

5




Figure 1




Figure 2

Configuration Process




Figure 3




Figure 4

SEE operation




Figure 6




Figure 5




Figure 7




Figure 8




Figure 9




Figure 10

PATENT
Docket No. 46659-20001.00

DECLARATION FOR UTILITY PATENT APPLICATION

AS A BELOW-NAMED INVENTOR, I HEREBY DECLARE THAT:

My residence, post office address, and citizenship is as stated below next to my name.

I believe I am the original, first of the subject matter which is claimed and for which a patent is sought on the invention entitled: **SYSTEM AND METHOD FOR ON-LINE SERVICE CREATION**, the specification of which is attached hereto unless the following box is checked:

☐ was filed on _____ as United States Application Serial No. or PCT International Application No. _____ and was amended on _____ (if applicable).

I HEREBY STATE THAT I HAVE REVIEWED AND UNDERSTAND THE CONTENTS OF THE ABOVE-IDENTIFIED SPECIFICATION, INCLUDING THE CLAIMS, AS AMENDED BY ANY AMENDMENT REFERRED TO ABOVE.

I acknowledge the duty to disclose information which is material to the patentability as defined in 37 C.F.R. § 1.56.

I hereby claim foreign priority benefits under 35 U.S.C. § 119(a)-(d) or § 365(b) of any foreign application(s) for patent or inventor's certificate, or § 365(a) of any PCT International application which designated at least one country other than the United States listed below and have also identified below, by checking the box, any foreign application for patent or inventor's certificate, or PCT International application having a filing date before that of the application on which priority is claimed:

Application No.	Country	Date of Filing (day/month/year)	Priority Claimed?
			<input type="checkbox"/> Yes <input type="checkbox"/> No

I hereby claim benefit under 35 U.S.C. § 119(e) of any United States provisional application(s) listed below:

Application Serial No.	Filing Date

I hereby claim the benefit under 35 U.S.C. § 120 of any United States application(s), or § 365(c) of any PCT International application designating the United States, listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States or PCT International application in the manner provided by the first paragraph of 35 U.S.C. § 112, we acknowledge the duty to disclose information which is material to

dc-222983

patentability as defined in 37 C.F.R. § 1.56 which became available between the filing date of the prior application and the national or PCT International filing date of this application.

Application Serial No.	Filing Date	Status
		<input type="checkbox"/> Patented <input type="checkbox"/> Pending <input type="checkbox"/> Abandoned

I hereby appoint the following attorneys and agents to prosecute this application and to transact all business in the Patent and Trademark Office connected therewith:

Laurie A. Axford (Reg No. 35,053)	Sanjay S. Bagade (Reg No. 42,280)
Joseph Barrera (Reg No. 44,522)	Erwin J. Basinski (Reg No. 34,773)
Shantanu Basu (Reg No. 43,318)	Richard R. Batt (Reg No. 43,485)
Frank P. Becking (Reg No. 42,309)	Vincent J. Belusko (Reg No. 30,820)
Kimberly A. Bolin (Reg No. 44,546)	Timothy J. Bortree (Reg No. 43,506)
Barry E. Bretschneider (Reg No. 28,055)	Tyler S. Brown (Reg No. 36,465)
Nicholas Buffinger (Reg No. 39,124)	Jingming Cai (Reg No. P-44,579)
Mark R. Carter (Reg No. 39,131)	Robert K. Cerpa (Reg No. 39,933)
Peng Chen (Reg No. 43,543)	Thomas Chuang (Reg No. P-44,616)
Thomas E. Ciotti (Reg No. 21,013)	Matthew M. D'Amore (Reg No. 42,457)
Raj S. Davé (Reg No. 42,465)	Stephen C. Durant (Reg No. 31,506)
Carolyn A. Favorito (Reg No. 39,183)	David L. Fehrman (Reg No. 28,600)
Hector Gallegos (Reg No. 40,614)	Debra J. Glaister (Reg No. 33,888)
Kenneth R. Glick (Reg No. 28,612)	Franklin Y. Han (Reg No. 41,055)
Charles D. Holland (Reg No. 35,196)	Peter Hsieh (Reg No. P-44,780)
Madeline I. Johnston (Reg No. 36,174)	Richard D. Jordan (Reg No. 33,519)
Ararat Kapovytian (Reg No. 40,044)	Richard C. Kim (Reg No. 40,046)
Kawai Lau (Reg No. 44,461)	Elaine K. Lee (Reg No. 41,936)
Richard H. Lilley (Reg No. 42,803)	Lisa E. Marks (Reg No. 44,901)
Thomas D. Mays (Reg No. 34,524)	Gladys H. Monroy (Reg No. 32,430)
Philip A. Morin (Reg No. P-45,926)	Kate H. Murashige (Reg No. 29,959)
Catherine M. Polizzi (Reg No. 40,130)	William C. Revelos (Reg No. 42,101)
Paul J. Riley (Reg No. 38,596)	Robert Saltzberg (Reg No. 36,910)
Debra A. Shetka (Reg No. 33,309)	Terri Shieh-Newton (Reg No. P-47,081)
Rebecca Shortle (Reg No. P47,083)	Kevin R. Spivak (Reg No. 43,148)
E. Thomas Wheelock (Reg No. 28,825)	Todd W. Wight (Reg No. 45,218)
Thomas G. Wiseman (Reg No. 35,046)	Frank Wu (Reg No. 41,386)
George C. Yu (Reg No. 44,418)	Karen R. Zachow (Reg No. P-46,332)

and:

Please direct all communications to:

Lisa E. Marks
Morrison & Foerster LLP
2000 Pennsylvania Avenue, N.W.
Washington, D.C. 20006-1888

